

**PRICING SCHEDULE****Attachment J2'**

<b>Renovation and repair of Men Restroom 214 H-Wing 2-floor</b>					
	<b>Quantity</b>	<b>Description</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Total</b>
1.	1	Construction site set up, installation of construction site security.	Lot		
2.	1	Demolition work of the old installation, including demolition and disposal of restroom furniture, old pipes (including wall demolition), and partitions. Demolition work for wall coverings and floor coverings, including tile disposal.	Lot		
3.	1	Material tile adhesive, plaster boards, corner rails and plaster work. Including water proof ground and wall insulation.	Lot		
4.	1	Laying wall and floor tiles including man power and material, joint material, floor level balancing. - Floor tiles (approx. 24 sq m), Type Villeroy & Boch R10 DT10 295*295mm. - Wall tiles Keratim (approx. 20 sq m): Deutsches Steinzeug Matt White, ca.200*240mm. - End rails for tile Level (approx. 15 m).	Lot		
5.	1	Produce silicone joints, including material and man power (approx. 35 m)	Lot		
6.	1	Installation of water and sewer line pipes, including material, insulation and man power. Installation of new hot water pipe for the pipe work, type Typ Geberit Mepla DN 15 -26). Installation of main water valve.	Lot		
7.	2	Installation of toilet flush cistern/under plaster, Type Geberite. One Installation of toilet bowl and seat, Type Ideal Standard Eurovit. One Installation of handicap toilet bowl and seat, Type Ideal Standard Eurovit. Installation of toilet water flush sensor, Type Geberite White, including material und connection pipes and waste water pipe.	Ea.		
8.	1	Installation of Urinal flush cistern/under plaster, Type Geberite Installation of toilet bowl and seat, Type Ideal Standard Eurovit. Installation of toilet water electronic flush sensor, Type Geberite White. Including material und connection pipes and waste water pipe.	Ea.		
9.	2	Installation of under plaster washbowl rack, Type Geberite. One installation of toilet washbowl 60cm, Type Ideal Standard Eurovit. One installation handicap of toilet washbowl 60cm, Type Ideal Standard Eurovit. Including material and man power.	Ea.		
10.	1	Indoor floor drain Type Kessel. Including material und connection pipes and waste water pipe.	Ea.		
11.	1	Installation of water faucet and connection pipes and solder work Type Hansa.	Ea.		

12.	1	Installation of new radiator.	Ea.		
13.	1	Installation of dry wall and installation wall.	Lot		
14.	1	Installation of partition walls Type META 40 FB for: (approx. 4 m) wall, 2 doors 100 cm & 70cm, Urine table, 1 urinal walls, including planning documents, cutting and assembly.	Lot		
15.	1	Delivery and installation of new water heater, Stiebel Etron 5kw, installation of all restroom Equipment.	Lot		
16.	1	End cleaning and Construction site visit and Inspection with FAC Employee Installation of Toilet equipment (soap dispenser, paper holder, toilet brush).	Lot		

Renovation and repair of Women Restroom 216 H-Wing 2-floor					
CLIN #	Quantity	Description	Unit	Unit Price	Total
1.	1	Construction site set up, installation of construction site security.	Lot		
2.	1	Demolition work of the old Installation. Including Demolition and disposal of restroom furniture, old pipes (Including wall demolition), and partitions. Demolition work for wall coverings and floor coverings, including tile disposal.	Lot		
3.	1	Material tile adhesive, plaster boards, corner rails and plaster work. Including water proof ground and wall insulation.	Lot		
4.	1	Laying wall and floor tiles including man power and material, joint material, floor level balancing. - Floor tiles (approx. 28 sq m), Type Villeroy & Boch R10 DT10 295*295mm. - Wall tiles Keratim (approx. 20 sq m): Deutsches Steinzeug Matt White ca.200*240mm. - End rails for tile Level (approx. 15 m).	Lot		
5.	1	Produce silicone joints, including material and man power (approx. 35 m).	Lot		
6.	1	Installation of water and sewer line pipes, including material, insulation and man power. Installation of new hot water pipe for the pipe work, type Typ Geberit Mepla DN 15 -26). Installation of main water valve.	Lot		
7.	2	Installation of toilet flush cistern/under plaster, Type Geberite. One installation of toilet bowl and seat, Type Ideal Standard Eurovit. One installation of handicap toilet bowl and seat, Type Ideal Standard Eurovit. Installation of toilet water flush sensor, Type Geberite White. Including material und connection pipes and waste water pipe.	Ea.		

8.	2	Installation of under plaster washbowl rack, Type Geberite. One installation of toilet washbowl 60cm, Type Ideal Standard Eurovit One installation of handicap toilet washbowl 60cm, Type Ideal Standard Eurovit. Including material and man power.	Ea.		
9.	1	Indoor floor drain Type Kessel. Including material und connection pipes and waste water pipe.	Ea.		
10.	2	Installation of water faucet and connection pipes and solder work, Type Hansa.	Ea.		
11.	1	Radiator. Installation of new radiator.	Ea.		
12.	1	Installation of dry wall and installation wall.	Lot		
13.	1	Installation of partition walls Type META 40 FB for: (approx. 6 m) wall, 2 doors 100 cm & 70cm, Urine table. Including planning documents, cutting and assembly.	Lot		
14.	1	Delivery and installation of new water heater, Stiebel Etron 5kw. Installation of all restroom equipment.	Lot		
15.	1	End cleaning and Construction site vised and Inspection with FAC Employee. Installation of Toilet equipment (soap dispenser, paper holder, toilet brush).	Lot		

Renovation and repair of Men Shower and Restroom G-Wing 008					
CLIN #	Quantity	Description	Unit	Unit Price	Total
1.	1	Construction site set up, installation of construction site security	Lot		
2.	1	Demolition work of the old Instillation, including demolition and disposal of bathroom furniture, old pipes (including wall demolition), and partitions. Demolition work for wall coverings and floor coverings, including tile disposal.	Lot		
3.	1	Material tile adhesive, plaster boards, corner rails and including plaster work. Including water proof ground and wall insulation for Shower area.	Lot		
4.	1	Laying wall and floor tiles including man power and material, joint material. - Floor tiles (approx. 30 sq m), Type Villeroy & Boch R10 DT10 295*295mm. - Wall tiles Keratim (approx. 35 sq m): Deutsches Steinzeug Matt White ca.200*240mm. - End rails for tile Level (approx. 15 m).	Lot		
5.	1	Produce silicone joints, including Material and man power (approx. 30 sq m).	Lot		

6.	1	Installation of water and sewer line pipes, including material, insulation and man power. Installation of new hot water pipe for the Shower About the sealing (approx. 15m pipe work type Typ Geberit Mepla DN 15 -26). Installation of main water valve.	Lot		
7.	1	Installation of toilet flush cistern/under plaster, Type Geberite. Installation of toilet toilet bowl and seat, Type Ideal Standard Eurovit. Installation of toilet water flush sensor, Type Geberite White. Including material und connection pipes and waste water pipe.	Ea.		
8.	3	Installation of under plaster washbowl rack, Type Geberite. Installation of toilet washbowl 60cm, Type Ideal Standard Eurovit. Water faucet Ideal TypeStandard CeraMix Blue Waschtischarmatur. Including material and man power	Ea.		
9.	1	Installation of Urinal flush cistern/under plaster, Type Geberite. Installation of toilet toilet bowl and seat, Type Ideal Standard Eurovit. Installation of toilet water electronic flush sensor, Type Geberite White. Including material und connection pipes and waste water pipe.	Ea.		
10.	1	Indoor floor drain Type Kessel. Including material und connection pipes and waste water pipe.	Ea.		
11.	1	Installation of installation wall (approx. 8 sq m) double-layered.	Lot		
12.	1	Installation of partition walls Type META 40 FB for: 1 Toilets (approx. 3 m) wall, 1 door 90 cm, 1 room separator (Urinal).	Lot		
13.	1	Installation of Shower tube Type Ideal Standard Eurovit, approx. (80cm*80cm), including material und connection pipes and waste water pipe. Water faucet Type Ideal Standard CeraMix Blue. Water save Shower head Type Ideal Standard. 2 Wings Shower door safety glass, including insulation. Including material and man power.	Ea.		
14.	1	Dry Wall installation (approx. 8 sq m), including wall finishing plaster work.	Lot		
15.	1	Installation of hot water boiler Type Stiebel Eltron 231252 Warmwasserspeicher, 50 Liter, SHZ 50, including material und connection pipes and waste water pipe. Sicherheitsgruppe KV30. Connection to the wall. Or Stiebel Eltron 13kW Water heater	Ea.		
16.	1	Installation of exhaust system, wall opening diameter, installation of fan, and exhaust pipe work.	Lot		
17.	1	End cleaning and Construction site visit and Inspection with FAC Employee.	Lot		
18.	1	Radiator, including thermostat and Installation.	Ea.		

Renovation and repair of Women Shower and Restroom G-Wing 011					
CLIN #	Quantity:	Description:	Unit:	Unit Price:	Total:
1.	1	Construction site set up, installation of construction site security.	Lot		
2.	1	Demolition work of the old Installation, including demolition and disposal of bathroom furniture, old pipes (including wall demolition), and partitions. Demolition work for wall coverings and floor coverings, including tile disposal.	Lot		
3.	1	Material tile adhesive, plaster boards, corner rails and including plaster work. Including water proof ground and wall insulation for Shower area.	Lot		
4.	1	Laying wall and floor tiles including man power and material, joint material. - Floor tiles (approx. 30 sq m), Type Villeroy & Boch R10 DT10 295*295mm. - Wall tiles Keratim (approx. 35 sq m): Deutsches Steinzeug Matt White ca.200*240mm. - End rails for tile Level (approx. 15 m.)	Lot		
5.	1	Produce silicone joints, including Material and man power (approx. 30 sq m)	Lot		
6.	1	Installation of water and sewer line pipes, including material, insulation and man power. Installation of new hot water pipe for the shower about the sealing (approx. 15m pipe work type Typ Geberit Mepla DN 15 -26). Installation of main water valve.	Lot		
7.	1	Installation of toilet flush cistern/under plaster, Type Geberite. Installation of toilet bowl and seat, Type Ideal Standard Eurovit. Installation of toilet water flush sensor, Type Geberite White. Including material und connection pipes and waste water pipe.	Ea.		
8.	3	Installation of under plaster washbowl rack, Type Geberite. Installation of toilet washbowl 60cm, Type Ideal Standard Eurovit. Water faucet Ideal Type Standard CeraMix Blue Waschtischarmatur. Including material and man power	Ea.		
9.	1	Indoor floor drain Type Kessel including material und connection pipes and waste water pipe.	Ea.		
10.	1	Installation of installation wall (approx. 8 sq m) double-layered.	Lot		
11.	1	Installation of partition walls Type META 40 FB for: 1 Toilets (approx. 3 m) wall, 1 doors 90 cm,.1 room separator (Urinal)	Lot		

12.	1	Installation of Shower tube Type Ideal Standard Eurovit, approx. (80cm*80cm), including material and connection pipes and waste water pipe. Water faucet Type Ideal Standard CeraMix Blue. Water save Shower head Type Ideal Standard. 2 Wings Shower door safety glass, including insulation. Including material and man power.	Ea.		
13.	1	Dry Wall installation (approx. 10 sq m), including wall finishing plaster work.	Lot		
14.	1	Installation of hot water boiler Type Stiebel Eltron 231252 Warmwasserspeicher, 50 Liter, SHZ 50, including material und connection pipes and waste water pipe. Sicherheitsgruppe KV30 Connection to the wall. Or Stiebel Eltron 13kW Water heater	Ea.		
15.	1	Installation of exhaust system, wall opening diameter, installation of fan, exhaust pipe work and ceiling cover.	Lot		
16.	1	End cleaning and Construction site vided and Inspection with FAC Employee.	Lot		
17.	1	Radiator, including thermostat and Installation.	Ea.		

**VALUE ADDED TAX** (if applicable):

\_\_\_\_\_

**DBA** (if applicable):

\_\_\_\_\_

**TOTAL VALUE OF CONTRACT:**

\_\_\_\_\_

**STATE CURRENCY:**

\_\_\_\_\_