

The Contractor shall complete all work, including furnishing all labor, material, equipment and services, required under this order for the firm fixed-price indicated below. This price shall include all labor, materials, and profit. Any costs not priced will be considered to be included in the overhead and other indirect costs.

PRICING			Quantity:	Net:	Total:
1	Remove topsoil and store at the side				
2	Manual excavation in the section of KV boxes and cable inlet to the building				
3	De-energization of KV boxes and cables, confirm all-poles are de-energized				
4	Secure positioning of KV boxes including concrete base frame, repair any damages				
5	Prepare, clean wall surface, remove loose plastering and fill in accordingly				
6	Sealing via bituminous thick film coating or bituminous sheeting				
7	Protection of sealing via dimpled sheeting				
8	Backfilling in layers manually or, where possible, also with a digger				
9	Foundation for KV boxes				
10	Gravel belts and edging stones to avoid moisture around the KV boxes				
11	Reconnect mains voltage to KV boxes				
Sub-Total:					
VAT 19%:					
Total:					
Currency					